

# APPENDIX E

(As mentioned earlier, the applicant will strive to manage water use to the absolute minimum. Presently, it is proposed that water will be bought and transported to site. The contractor will be encouraged to consider the use of non-potable water for the activities. The use of solar power should also be considered as an alternative power source to the offices and/or workshops.

The general waste to be generated at the site will mainly consist of paper, plastic, tin, and/or glass from the office area. All general waste will be contained in sealable refuse bins that will be placed at the office area until it is transported to a recognised general waste landfill site.

A recognized contractor will service the chemical toilets and be responsible for the removal of the sewerage to a registered sewerage handling facility.

Hazardous waste may result from accidental spillages/breakdowns. Such contaminated areas will immediately (within two hours of occurrence) be cleaned and the contaminated soil will be contained in a designated hazardous waste container until it is removed from site by a registered hazardous waste handling contractor to an approved facility. No waste will be disposed of, buried, burned or treated on the site.)

